



## **KZN is in dire need of well-built high-density housing.**

Echo is the suspended flooring solution to this problem, installing 200-400m<sup>2</sup> per day. Once the slab is grouted, the brickwork above may go ahead 24-48 hours later. The most economic design involves walls above walls, with 220mm walls bearing the load and 110mm walls supported by the slab. Another benefit of the system is that there is no topping required only a 50mm screed with ref 100 mesh. This slab system doesn't need propping.



*Creating the perfect solution is key.*